

§ 250.1004

30 CFR Ch. II (7-1-03 Edition)

pipeline if the Regional Supervisor determines that such burial will reduce the likelihood of environmental degradation or that the pipeline may constitute a hazard to trawling operations or other uses. A trawl test or diver survey may be required to determine whether or not pipeline burial is necessary or to determine whether a pipeline has been properly buried.

(2) Pipeline valves, taps, tie-ins, capped lines, and repaired sections that could be obstructive shall be provided with at least 3 feet of cover unless the Regional Supervisor determines that such items present no hazard to trawling or other operations. A protective device may be used to cover an obstruction in lieu of burial if it is approved by the Regional Supervisor prior to installation.

(3) Pipelines shall be installed with a minimum separation of 18 inches at pipeline crossings and from obstructions.

(4) Pipeline risers installed after April 1, 1988, shall be protected from physical damage that could result from contact with floating vessels. Riser protection on pipelines installed on or before April 1, 1988, may be required when the Regional Supervisor determines that significant damage potential exists.

(b)(1) Pipelines shall be hydrostatically tested with water at a stabilized pressure of at least 1.25 times the MAOP for at least 8 hours when installed, relocated, uprated, or reactivated after being out-of-service for more than 1 year.

(2) Prior to returning a pipeline to service after a repair, the pipeline shall be pressure tested with water or processed natural gas at a minimum stabilized pressure of at least 1.25 times the MAOP for at least 2 hours.

(3) Pipelines shall not be pressure tested at a pressure which produces a stress in the pipeline in excess of 95 percent of the specified minimum-yield strength of the pipeline. A temperature recorder measuring test fluid temperature synchronized with a pressure recorder along with deadweight test readings shall be employed for all pressure testing. When a pipeline is pressure tested, no observable leakage shall be allowed. Pressure gauges and record-

ers shall be of sufficient accuracy to verify that leakage is not occurring.

(4) The Regional Supervisor may require pressure testing of pipelines to verify the integrity of the system when the Regional Supervisor determines that there is a reasonable likelihood that the line has been damaged or weakened by external or internal conditions.

(c) When a pipeline is repaired utilizing a clamp, the clamp shall be a full encirclement clamp able to withstand the anticipated pipeline pressure.

[53 FR 10690, Apr. 1, 1988; 53 FR 12227, Apr. 13, 1988; 57 FR 26997, June 17, 1992. Redesignated at 63 FR 29479, May 29, 1998]

§ 250.1004 Safety equipment requirements for DOI pipelines.

(a) The lessee shall ensure the proper installation, operation, and maintenance of safety devices required by this section on all incoming, departing, and crossing pipelines on platforms.

(b)(1)(i) Incoming pipelines to a platform shall be equipped with a flow safety valve (FSV).

(ii) For sulphur operations, incoming pipelines delivering gas to the power plant platform may be equipped with high- and low-pressure sensors (PSHL), which activate audible and visual alarms in lieu of requirements in paragraph (b)(1)(i) of this section. The PSHL shall be set at 15 percent or 5 psi, whichever is greater, above and below the normal operating pressure range.

(2) Incoming pipelines boarding to a production platform shall be equipped with an automatic shutdown valve (SDV) immediately upon boarding the platform. The SDV shall be connected to the automatic- and remote-emergency shut-in systems.

(3) Departing pipelines receiving production from production facilities shall be protected by high- and low-pressure sensors (PSHL) to directly or indirectly shut in all production facilities. The PSHL shall be set not to exceed 15 percent above and below the normal operating pressure range. However, high pilots shall not be set above the pipeline's MAOP.

(4) Crossing pipelines on production or manned nonproduction platforms which do not receive production from the platform shall be equipped with an

Minerals Management Service, Interior

§ 250.1007

SDV immediately upon boarding the platform. The SDV shall be operated by a PSHL on the departing pipelines and connected to the platform automatic- and remote-emergency shut-in systems.

(5) The Regional Supervisor may require that oil pipelines be equipped with a metering system to provide a continuous volumetric comparison between the input to the line at the structure(s) and the deliveries onshore. The system shall include an alarm system and shall be of adequate sensitivity to detect variations between input and discharge volumes. In lieu of the foregoing, a system capable of detecting leaks in the pipeline may be substituted with the approval of the Regional Supervisor.

(6) Pipelines incoming to a subsea tie-in shall be equipped with a block valve and an FSV. Bidirectional pipelines connected to a subsea tie-in shall be equipped with only a block valve.

(7) Gas-lift or water-injection pipelines on unmanned platforms need only be equipped with an FSV installed immediately upstream of each casing annulus or the first inlet valve on the christmas tree.

(8) Bidirectional pipelines shall be equipped with a PSHL and an SDV immediately upon boarding each platform.

(9) Pipeline pumps must comply with section A7 of API RP 14C (incorporated by reference as specified in §250.198). The setting levels for the PSHL devices are specified in paragraph (b)(3) of this section.

(c) If the required safety equipment is rendered ineffective or removed from service on pipelines which are continued in operation, an equivalent degree of safety shall be provided. The safety equipment shall be identified by the placement of a sign on the equipment stating that the equipment is rendered ineffective or removed from service.

[53 FR 10690, Apr. 1, 1988, as amended at 54 FR 50617, Dec. 8, 1989; 56 FR 32100, July 15, 1991. Redesignated at 63 FR 29479, May 29, 1998; 67 FR 51760, Aug. 9, 2002]

§ 250.1005 Inspection requirements for DOI pipelines.

(a) Pipeline routes shall be inspected at time intervals and methods pre-

scribed by the Regional Supervisor for indication of pipeline leakage. The results of these inspections shall be retained for at least 2 years and be made available to the Regional Supervisor upon request.

(b) When pipelines are protected by rectifiers or anodes for which the initial life expectancy of the cathodic protection system either cannot be calculated or calculations indicate a life expectancy of less than 20 years, such pipelines shall be inspected annually by taking measurements of pipe-to-electrolyte potential measurements.

§ 250.1006 How must I decommission and take out of service a DOI pipeline?

(a) The requirements for decommissioning pipelines are listed in §250.1750 through §250.1754.

(b) The table in this section lists the requirements if you take a DOI pipeline out of service:

If you have the pipeline out of service for:	Then you must:
(1) 1 year or less	Isolate the pipeline with a blind flange or a closed block valve at each end of the pipeline.
(2) More than 1 year but less than 5 years.	Flush and fill the pipeline with inhibited seawater.
(3) 5 or more years	Decommission the pipeline according to §§ 250.1750–250.1754.

[67 FR 35405, May 17, 2002]

§ 250.1007 What to include in applications.

(a) Applications to install a lease term pipeline or for a pipeline right-of-way grant must be submitted in quadruplicate to the Regional Supervisor. Right-of-way grant applications must include an identification of the operator of the pipeline. Each application must include the following:

(1) Plat(s) drawn to a scale specified by the Regional Supervisor showing major features and other pertinent data including area, lease, and block designations; water depths; route; length in Federal waters; width of right-of-way, if applicable; connecting facilities; size; product(s) to be transported with anticipated gravity or density; burial depth; direction of flow; X-Y coordinates of key points; and the location of other pipelines that will be