

**§ 250.420**

(d) A Hydrogen Sulfide Contingency Plan (see § 250.490), if applicable, and not previously submitted;

(e) A welding plan (see §§ 250.109 to 250.113) if not previously submitted;

(f) In areas subject to subfreezing conditions, evidence that the drilling equipment, BOP systems and components, diverter systems, and other associated equipment and materials are suitable for operating under such conditions;

(g) A request for approval if you plan to wash out or displace some cement to facilitate casing removal upon well abandonment; and

(h) Such other information as the District Supervisor may require.

[68 FR 8423, Feb. 20, 2003]

CASING AND CEMENTING REQUIREMENTS

**§ 250.420 What well casing and cementing requirements must I meet?**

You must case and cement all wells. Your casing and cementing programs must meet the requirements of this section and of §§ 250.421 through 250.428.

(a) *Casing and cementing program requirements.* Your casing and cementing programs must:

- (1) Properly control formation pressures and fluids;
- (2) Prevent the direct or indirect release of fluids from any stratum through the wellbore into offshore waters;
- (3) Prevent communication between separate hydrocarbon-bearing strata;
- (4) Protect freshwater aquifers from contamination; and
- (5) Support unconsolidated sediments.

(b) *Casing requirements.* (1) You must design casing (including liners) to withstand the anticipated stresses imposed by tensile, compressive, and buckling loads; burst and collapse pressures; thermal effects; and combinations thereof.

(2) The casing design must include safety measures that ensure well control during drilling and safe operations during the life of the well.

(c) *Cementing requirements.* You must design and conduct your cementing jobs so that cement composition, placement techniques, and waiting times ensure that the cement placed

**30 CFR Ch. II (7-1-03 Edition)**

behind the bottom 500 feet of casing attains a minimum compressive strength of 500 psi before drilling out of the casing or before commencing completion operations.

[68 FR 8423, Feb. 20, 2003]

**§ 250.421 What are the casing and cementing requirements by type of casing string?**

The table in this section identifies specific design, setting, and cementing requirements for casing strings and liners. For the purposes of subpart D, the casing strings in order of normal installation are as follows: drive or structural, conductor, surface, intermediate, and production casings (including liners). The District Supervisor may approve or prescribe other casing and cementing requirements where appropriate.

Casing type	Casing requirements	Cementing requirements
(a) Drive or Structural.	Set by driving, jetting, or drilling to the minimum depth as approved or prescribed by the District Supervisor.	If you drilled a portion of this hole, you must use enough cement to fill the annular space back to the mudline.
(b) Conductor.	Design casing and select setting depths based on relevant engineering and geologic factors. These factors include the presence or absence of hydrocarbons, potential hazards, and water depths. Set casing immediately before drilling into formations known to contain oil or gas. If you encounter oil or gas or unexpected formation pressure before the planned casing point, you must set casing immediately	Use enough cement to fill the calculated annular space back to the mudline. Verify annular fill by observing cement returns. If you cannot observe cement returns, use additional cement to ensure fill-back to the mudline. For drilling on an artificial island or when using a glory hole, you must discuss the cement fill level with the District Supervisor.