

**§ 250.515**

**30 CFR Ch. II (7–1–03 Edition)**

collars that may be pulled prior to filling the hole and the equivalent well-control fluid volume shall be calculated and posted near the operator's station. A mechanical, volumetric, or electronic device for measuring the amount of well-control fluid required to fill the hole shall be utilized.

**§ 250.515 Blowout prevention equipment.**

(a) The BOP system and system components and related well-control equipment shall be designed, used, maintained, and tested in a manner necessary to assure well control in foreseeable conditions and circumstances, including subfreezing conditions. The

working pressure rating of the BOP system and BOP system components shall exceed the expected surface pressure to which they may be subjected. If the expected surface pressure exceeds the rated working pressure of the annular preventer, the lessee shall submit with Form MMS-124 or Form MMS-123, as appropriate, a well-control procedure that indicates how the annular preventer will be utilized, and the pressure limitations that will be applied during each mode of pressure control.

(b) The minimum BOP system for well-completion operations must meet the appropriate standards from the following table:

When	The minimum BOP stack must include
(1) The expected pressure is less than 5,000 psi.	Three BOPs consisting of an annular, one set of pipe rams, and one set of blind or blind-shear rams.
(2) The expected pressure is 5,000 psi or greater or you use multiple tubing strings.	Four BOPs consisting of an annular, two sets of pipe rams, and one set of blind or blind-shear rams.
(3) You handle multiple tubing strings simultaneously.	Four BOPs consisting of an annular, one set of pipe rams, one set of dual pipe rams, and one set of blind or blind-shear rams.
(4) You use a tapered drill string .....	At least one set of pipe rams that are capable of sealing around each size of drill string. If the expected pressure is greater than 5,000 psi, then you must have at least two sets of pipe rams that are capable of sealing around the larger size drill string. You may substitute one set of variable bore rams for two sets of pipe rams.
(5) It is after February 21, 2006 .....	At least one set of blind-shear rams. The blind-shear rams must be capable of shearing the drill pipe or tubing in the hole.

(c) The BOP systems for well completions shall be equipped with the following:

(1) A hydraulic-actuating system that provides sufficient accumulator capacity to supply 1.5 times the volume necessary to close all BOP equipment units with a minimum pressure of 200 psi above the precharge pressure without assistance from a charging system. No later than December 1, 1988, accumulator regulators supplied by rig air and without a secondary source of pneumatic supply, shall be equipped with manual overrides, or alternately, other devices provided to ensure capability of hydraulic operations if rig air is lost.

(2) A secondary power source, independent from the primary power source, with sufficient capacity to close all BOP system components and hold them closed.

(3) Locking devices for the pipe-ram preventers.

(4) At least one remote BOP-control station and one BOP-control station on the rig floor.

(5) A choke line and a kill line each equipped with two full opening valves and a choke manifold. At least one of the valves on the choke line shall be remotely controlled. At least one of the valves on the kill line shall be remotely controlled, except that a check valve on the kill line in lieu of the remotely controlled valve may be installed provided that two readily accessible manual valves are in place and the check valve is placed between the manual valves and the pump. This equipment shall have a pressure rating at least equivalent to the ram preventers.

(d) An inside BOP or a spring-loaded, back-pressure safety valve and an essentially full-opening, work-string safety valve in the open position shall be maintained on the rig floor at all times during well-completion operations. A wrench to fit the work-string

safety valve shall be readily available. Proper connections shall be readily available for inserting valves in the work string.

[53 FR 10690, Apr. 1, 1988, as amended at 54 FR 50616, Dec. 8, 1989; 58 FR 49928, Sept. 24, 1993. Redesignated at 62 FR 29479, May 29, 1998, as amended at 68 FR 8434, Feb. 20, 2003]

**§ 250.516 Blowout preventer system tests, inspections, and maintenance.**

(a) *BOP pressure testing timeframes.* You must pressure test your BOP system:

- (1) When installed; and
- (2) Before 14 days have elapsed since your last BOP pressure test. You must begin to test your BOP system before 12 a.m. (midnight) on the 14th day following the conclusion of the previous test. However, the District Supervisor may require testing every 7 days if conditions or BOP performance warrant.

(b) *BOP test pressures.* When you test the BOP system, you must conduct a low pressure and a high pressure test for each BOP component. Each individual pressure test must hold pressure long enough to demonstrate that the tested component(s) holds the required pressure. The District Supervisor may approve or require other test pressures or practices. Required test pressures are as follows:

- (1) All low pressure tests must be between 200 and 300 psi. Any initial pressure above 300 psi must be bled back to a pressure between 200 and 300 psi before starting the test. If the initial pressure exceeds 500 psi, you must bleed back to zero and reinitiate the test. You must conduct the low pressure test before the high pressure test.

(2) For ram-type BOP's, choke manifold, and other BOP equipment, the high pressure test must equal the rated working pressure of the equipment.

(3) For annular-type BOP's, the high pressure test must equal 70 percent of the rated working pressure of the equipment.

(c) *Duration of pressure test.* Each test must hold the required pressure for 5 minutes.

- (1) For surface BOP systems and surface equipment of a subsea BOP system, a 3-minute test duration is acceptable if you record your test pressures on the outermost half of a 4-hour

chart, on a 1-hour chart, or on a digital recorder.

(2) If the equipment does not hold the required pressure during a test, you must remedy the problem and retest the affected component(s).

(d) *Additional BOP testing requirements.* You must:

(1) Use water to test the surface BOP system;

(2) Stump test a subsurface BOP system before installation. You must use water to stump test a subsea BOP system. You may use drilling or completion fluids to conduct subsequent tests of a subsea BOP system;

(3) Alternate tests between control stations and pods. If a control station or pod is not functional, you must suspend further completion operations until that station or pod is operable;

(4) Pressure test the blind or blind-shear ram at least every 30 days;

(5) Function test annulars and rams every 7 days;

(6) Pressure-test variable bore-pipe rams against all sizes of pipe in use, excluding drill collars and bottom-hole tools; and

(7) Test affected BOP components following the disconnection or repair of any well-pressure containment seal in the wellhead or BOP stack assembly;

(e) *Postponing BOP tests.* You may postpone a BOP test if you have well-control problems. You must conduct the required BOP test as soon as possible (i.e., first trip out of the hole) after the problem has been remedied. You must record the reason for postponing any test in the driller's report.

(f) *Weekly crew drills.* You must conduct a weekly drill to familiarize all personnel engaged in well-completion operations with appropriate safety measures.

(g) *BOP inspections.* You must visually inspect your BOP system and marine riser at least once each day if weather and sea conditions permit. You may use television cameras to inspect this equipment. The District Supervisor may approve alternate methods and frequencies to inspect a marine riser.

(h) *BOP maintenance.* You must maintain your BOP system to ensure that the equipment functions properly.