

§ 146.66

40 CFR Ch. I (7-1-03 Edition)

the casing to the surface, using a minimum of 120% of the calculated annual volume. The Director may require more than 120% when the geology or other circumstances warrant it.

(3) At least one long string casing, using a sufficient number of centralizers, shall extend to the injection zone and shall be cemented by circulating cement to the surface in one or more stages:

(i) Of sufficient quantity and quality to withstand the maximum operating pressure; and

(ii) In a quantity no less than 120% of the calculated volume necessary to fill the annular space. The Director may require more than 120% when the geology or other circumstances warrant it.

(4) Circulation of cement may be accomplished by staging. The Director may approve an alternative method of cementing in cases where the cement cannot be recirculated to the surface, provided the owner or operator can demonstrate by using logs that the cement is continuous and does not allow fluid movement behind the well bore.

(5) Casings, including any casing connections, must be rated to have sufficient structural strength to withstand, for the design life of the well:

(i) The maximum burst and collapse pressures which may be experienced during the construction, operation and closure of the well; and

(ii) The maximum tensile stress which may be experienced at any point along the length of the casing during the construction, operation, and closure of the well.

(6) At a minimum, cement and cement additives must be of sufficient quality and quantity to maintain integrity over the design life of the well.

(d) *Tubing and packer.* (1) All Class I hazardous waste injection wells shall inject fluids through tubing with a packer set at a point specified by the Director.

(2) In determining and specifying requirements for tubing and packer, the following factors shall be considered:

- (i) Depth of setting;
- (ii) Characteristics of injection fluid (chemical content, corrosiveness, temperature and density);
- (iii) Injection pressure;
- (iv) Annular pressure;

(v) Rate (intermittent or continuous), temperature and volume of injected fluid;

(vi) Size of casing; and

(vii) Tubing tensile, burst, and collapse strengths.

(3) The Director may approve the use of a fluid seal if he determines that the following conditions are met:

(i) The operator demonstrates that the seal will provide a level of protection comparable to a packer;

(ii) The operator demonstrates that the staff is, and will remain, adequately trained to operate and maintain the well and to identify and interpret variations in parameters of concern;

(iii) The permit contains specific limitations on variations in annular pressure and loss of annular fluid;

(iv) The design and construction of the well allows continuous monitoring of the annular pressure and mass balance of annular fluid; and

(v) A secondary system is used to monitor the interface between the annulus fluid and the injection fluid and the permit contains requirements for testing the system every three months and recording the results.

§ 146.66 Logging, sampling, and testing prior to new well operation.

(a) During the drilling and construction of a new Class I hazardous waste injection well, appropriate logs and tests shall be run to determine or verify the depth, thickness, porosity, permeability, and rock type of, and the salinity of any entrained fluids in, all relevant geologic units to assure conformance with performance standards in §146.65, and to establish accurate baseline data against which future measurements may be compared. A descriptive report interpreting results of such logs and tests shall be prepared by a knowledgeable log analyst and submitted to the Director. At a minimum, such logs and tests shall include:

(1) Deviation checks during drilling on all holes constructed by drilling a pilot hole which are enlarged by reaming or another method. Such checks shall be at sufficiently frequent intervals to determine the location of the borehole and to assure that vertical avenues for fluid movement in the

Environmental Protection Agency

§ 146.67

form of diverging holes are not created during drilling; and

(2) Such other logs and tests as may be needed after taking into account the availability of similar data in the area of the drilling site, the construction plan, and the need for additional information that may arise from time to time as the construction of the well progresses. At a minimum, the following logs shall be required in the following situations:

(i) Upon installation of the surface casing:

(A) Resistivity, spontaneous potential, and caliper logs before the casing is installed; and

(B) A cement bond and variable density log, and a temperature log after the casing is set and cemented.

(ii) Upon installation of the long string casing:

(A) Resistivity, spontaneous potential, porosity, caliper, gamma ray, and fracture finder logs before the casing is installed; and

(B) A cement bond and variable density log, and a temperature log after the casing is set and cemented.

(iii) The Director may allow the use of an alternative to the above logs when an alternative will provide equivalent or better information; and

(3) A mechanical integrity test consisting of:

(i) A pressure test with liquid or gas;

(ii) A radioactive tracer survey;

(iii) A temperature or noise log;

(iv) A casing inspection log, if required by the Director; and

(v) Any other test required by the Director.

(b) Whole cores or sidewall cores of the confining and injection zones and formation fluid samples from the injection zone shall be taken. The Director may accept cores from nearby wells if the owner or operator can demonstrate that core retrieval is not possible and that such cores are representative of conditions at the well. The Director may require the owner or operator to core other formations in the borehole.

(c) The fluid temperature, pH, conductivity, pressure and the static fluid level of the injection zone must be recorded.

(d) At a minimum, the following information concerning the injection and

confining zones shall be determined or calculated for Class I hazardous waste injection wells:

(1) Fracture pressure;

(2) Other physical and chemical characteristics of the injection and confining zones; and

(3) Physical and chemical characteristics of the formation fluids in the injection zone.

(e) Upon completion, but prior to operation, the owner or operator shall conduct the following tests to verify hydrogeologic characteristics of the injection zone:

(1) A pump test; or

(2) Injectivity tests.

(f) The Director shall have the opportunity to witness all logging and testing by this subpart. The owner or operator shall submit a schedule of such activities to the Director 30 days prior to conducting the first test.

§ 146.67 Operating requirements.

(a) Except during stimulation, the owner or operator shall assure that injection pressure at the wellhead does not exceed a maximum which shall be calculated so as to assure that the pressure in the injection zone during injection does not initiate new fractures or propagate existing fractures in the injection zone. The owner or operator shall assure that the injection pressure does not initiate fractures or propagate existing fractures in the confining zone, nor cause the movement of injection or formation fluids into a USDW.

(b) Injection between the outermost casing protecting USDWs and the well bore is prohibited.

(c) The owner or operator shall maintain an annulus pressure that exceeds the operating injection pressure, unless the Director determines that such a requirement might harm the integrity of the well. The fluid in the annulus shall be noncorrosive, or shall contain a corrosion inhibitor.

(d) The owner or operator shall maintain mechanical integrity of the injection well at all times.

(e) Permit requirements for owners or operators of hazardous waste wells which inject wastes which have the potential to react with the injection formation to generate gases shall include: