

would be significantly changed by their omission.

(f) Provide the technical basis for either inclusion or exclusion of degradation, deterioration, or alteration processes of engineered barriers in the performance assessment, including those processes that would adversely affect the performance of natural barriers. Degradation, deterioration, or alteration processes of engineered barriers must be evaluated in detail if the magnitude and time of the resulting radiological exposures to the reasonably maximally exposed individual, or radionuclide releases to the accessible environment, would be significantly changed by their omission.

(g) Provide the technical basis for models used in the performance assessment such as comparisons made with outputs of detailed process-level models and/or empirical observations (e.g., laboratory testing, field investigations, and natural analogs).

§ 63.115 Requirements for multiple barriers.

Demonstration of compliance with § 63.113(a) must:

(a) Identify those design features of the engineered barrier system, and natural features of the geologic setting, that are considered barriers important to waste isolation.

(b) Describe the capability of barriers, identified as important to waste isolation, to isolate waste, taking into account uncertainties in characterizing and modeling the behavior of the barriers.

(c) Provide the technical basis for the description of the capability of barriers, identified as important to waste isolation, to isolate waste. The technical basis for each barrier's capability shall be based on and consistent with the technical basis for the performance assessments used to demonstrate compliance with § 63.113(b) and (c).

LAND OWNERSHIP AND CONTROL

§ 63.121 Requirements for ownership and control of interests in land.

(a) *Ownership of land.* (1) The geologic repository operations area must be located in and on lands that are either acquired lands under the jurisdiction

and control of DOE, or lands permanently withdrawn and reserved for its use.

(2) These lands must be held free and clear of all encumbrances, if significant, such as:

(i) Rights arising under the general mining laws;

(ii) Easements for right-of-way; and

(iii) All other rights arising under lease, rights of entry, deed, patent, mortgage, appropriation, prescription, or otherwise.

(b) *Additional controls for permanent closure.* Appropriate controls must be established outside of the geologic repository operations area. DOE shall exercise any jurisdiction and control over surface and subsurface estates necessary to prevent adverse human actions that could significantly reduce the geologic repository's ability to achieve isolation. The rights of DOE may take the form of appropriate possessory interests, servitudes, or withdrawals from location or patent under the general mining laws.

(c) *Additional controls through permanent closure.* Appropriate controls must be established outside the geologic repository operations area. DOE shall exercise any jurisdiction or control of activities necessary to ensure the requirements at § 63.111(a) and (b) are met. Control includes the authority to exclude members of the public, if necessary.

(d) *Water rights.* (1) DOE shall also have obtained such water rights as may be needed to accomplish the purpose of the geologic repository operations area.

(2) Water rights are included in the additional controls to be established under paragraph (b) of this section.

Subpart F—Performance Confirmation Program

§ 63.131 General requirements.

(a) The performance confirmation program must provide data that indicate, where practicable, whether:

(1) Actual subsurface conditions encountered and changes in those conditions during construction and waste emplacement operations are within the limits assumed in the licensing review; and

(2) Natural and engineered systems and components required for repository operation, and that are designed or assumed to operate as barriers after permanent closure, are functioning as intended and anticipated.

(b) The program must have been started during site characterization, and it will continue until permanent closure.

(c) The program must include in situ monitoring, laboratory and field testing, and in situ experiments, as may be appropriate to provide the data required by paragraph (a) of this section.

(d) The program must be implemented so that:

(1) It does not adversely affect the ability of the geologic and engineered elements of the geologic repository to meet the performance objectives.

(2) It provides baseline information and analysis of that information on those parameters and natural processes pertaining to the geologic setting that may be changed by site characterization, construction, and operational activities.

(3) It monitors and analyzes changes from the baseline condition of parameters that could affect the performance of a geologic repository.

§ 63.132 Confirmation of geotechnical and design parameters.

(a) During repository construction and operation, a continuing program of surveillance, measurement, testing, and geologic mapping must be conducted to ensure that geotechnical and design parameters are confirmed and to ensure that appropriate action is taken to inform the Commission of design changes needed to accommodate actual field conditions encountered.

(b) Subsurface conditions must be monitored and evaluated against design assumptions.

(c) Specific geotechnical and design parameters to be measured or observed, including any interactions between natural and engineered systems and components, must be identified in the performance confirmation plan.

(d) These measurements and observations must be compared with the original design bases and assumptions. If significant differences exist between the measurements and observations

and the original design bases and assumptions, the need for modifications to the design or in construction methods must be determined and these differences, their significance to repository performance, and the recommended changes reported to the Commission.

(e) In situ monitoring of the thermomechanical response of the underground facility must be conducted until permanent closure, to ensure that the performance of the geologic and engineering features is within design limits.

§ 63.133 Design testing.

(a) During the early or developmental stages of construction, a program for testing of engineered systems and components used in the design, such as, for example, borehole and shaft seals, backfill, and drip shields, as well as the thermal interaction effects of the waste packages, backfill, drip shields, rock, and unsaturated zone and saturated zone water, must be conducted.

(b) The testing must be initiated as early as practicable.

(c) If backfill is included in the repository design, a test must be conducted to evaluate the effectiveness of backfill placement and compaction procedures against design requirements before permanent backfill placement is begun.

(d) Tests must be conducted to evaluate the effectiveness of borehole, shaft, and ramp seals before full-scale operation proceeds to seal boreholes, shafts, and ramps.

§ 63.134 Monitoring and testing waste packages.

(a) A program must be established at the geologic repository operations area for monitoring the condition of the waste packages. Waste packages chosen for the program must be representative of those to be emplaced in the underground facility.

(b) Consistent with safe operation at the geologic repository operations area, the environment of the waste packages selected for the waste package monitoring program must be representative of the environment in which the wastes are to be emplaced.