

Nuclear Regulatory Commission

§ 60.150

(4) It provides an established plan for feedback and analysis of data, and implementation of appropriate action.

§ 60.141 Confirmation of geotechnical and design parameters.

(a) During repository construction and operation, a continuing program of surveillance, measurement, testing, and geologic mapping shall be conducted to ensure that geotechnical and design parameters are confirmed and to ensure that appropriate action is taken to inform the Commission of changes needed in design to accommodate actual field conditions encountered.

(b) Subsurface conditions shall be monitored and evaluated against design assumptions.

(c) As a minimum, measurements shall be made of rock deformations and displacement, changes in rock stress and strain, rate and location of water inflow into subsurface areas, changes in groundwater conditions, rock pore water pressures including those along fractures and joints, and the thermal and thermomechanical response of the rock mass as a result of development and operations of the geologic repository.

(d) These measurements and observations shall be compared with the original design bases and assumptions. If significant differences exist between the measurements and observations and the original design bases and assumptions, the need for modifications to the design or in construction methods shall be determined and these differences and the recommended changes reported to the Commission.

(e) In situ monitoring of the thermomechanical response of the underground facility shall be conducted until permanent closure to ensure that the performance of the natural and engineering features are within design limits.

§ 60.142 Design testing.

(a) During the early or developmental stages of construction, a program for in situ testing of such features as borehole and shaft seals, backfill, and the thermal interaction effects of the waste packages, backfill, rock, and groundwater shall be conducted.

(b) The testing shall be initiated as early as is practicable.

(c) A backfill test section shall be constructed to test the effectiveness of backfill placement and compaction procedures against design requirements before permanent backfill placement is begun.

(d) Test sections shall be established to test the effectiveness of borehole and shaft seals before full-scale operation proceeds to seal boreholes and shafts.

§ 60.143 Monitoring and testing waste packages.

(a) A program shall be established at the geologic repository operations area for monitoring the condition of the waste packages. Waste packages chosen for the program shall be representative of those to be emplaced in the underground facility.

(b) Consistent with safe operation at the geologic repository operations area, the environment of the waste packages selected for the waste package monitoring program shall be representative of the environment in which the wastes are to be emplaced.

(c) The waste package monitoring program shall include laboratory experiments which focus on the internal condition of the waste packages. To the extent practical, the environment experienced by the emplaced waste packages within the underground facility during the waste package monitoring program shall be duplicated in the laboratory experiments.

(d) The waste package monitoring program shall continue as long as practical up to the time of permanent closure.

Subpart G—Quality Assurance

SOURCE: 48 FR 28228, June 21, 1983, unless otherwise noted.

§ 60.150 Scope.

As used in this part, *quality assurance* comprises all those planned and systematic actions necessary to provide adequate confidence that the geologic repository and its subsystems or components will perform satisfactorily in service. Quality assurance includes quality control, which comprises those