

gaseous measurements and the engine’s known or assumed fuel properties. The target value for any compensation algorithm is 0.0% (that is, no bias high and no bias low), regardless of the uncompensated signal’s bias.

Subpart D—Calibrations and Verifications

§ 1065.301 Overview and general provisions.

(a) This subpart describes required and recommended calibrations and verifications of measurement systems. See subpart C of this part for specifications that apply to individual instruments.

(b) You must generally use complete measurement systems when performing calibrations or verifications in this subpart. For example, this would generally involve evaluating instruments based on values recorded with the complete system you use for recording test data, including analog-to-digital converters. For some calibrations and

verifications, we may specify that you disconnect part of the measurement system to introduce a simulated signal.

(c) If we do not specify a calibration or verification for a portion of a measurement system, calibrate that portion of your system and verify its performance at a frequency consistent with any recommendations from the measurement-system manufacturer, consistent with good engineering judgment.

(d) Use NIST-traceable standards to the tolerances we specify for calibrations and verifications. Where we specify the need to use NIST-traceable standards, you may alternatively ask for our approval to use international standards that are not NIST-traceable.

§ 1065.303 Summary of required calibration and verifications.

The following table summarizes the required and recommended calibrations and verifications described in this subpart and indicates when these have to be performed:

TABLE 1 OF § 1065.303—SUMMARY OF REQUIRED CALIBRATION AND VERIFICATIONS

Type of calibration or verification	Minimum frequency ^a
§ 1065.305: accuracy, repeatability and noise.	<i>Accuracy:</i> Not required, but recommended for initial installation. <i>Repeatability:</i> Not required, but recommended for initial installation. <i>Noise:</i> Not required, but recommended for initial installation.
§ 1065.307: linearity	<i>Speed:</i> Upon initial installation, within 370 days before testing and after major maintenance. <i>Torque:</i> Upon initial installation, within 370 days before testing and after major maintenance. <i>Electrical power:</i> Upon initial installation, within 370 days before testing and after major maintenance. <i>Clean gas and diluted exhaust flows:</i> Upon initial installation, within 370 days before testing and after major maintenance, unless flow is verified by propane check or by carbon or oxygen balance. <i>Raw exhaust flow:</i> Upon initial installation, within 185 days before testing and after major maintenance, unless flow is verified by propane check or by carbon or oxygen balance. <i>Gas analyzers:</i> Upon initial installation, within 35 days before testing and after major maintenance. <i>PM balance:</i> Upon initial installation, within 370 days before testing and after major maintenance. <i>Stand-alone pressure and temperature:</i> Upon initial installation, within 370 days before testing and after major maintenance.
§ 1065.308: Continuous analyzer system response and recording.	Upon initial installation, after system reconfiguration, and after major maintenance.
§ 1065.309: Continuous analyzer uniform response.	Upon initial installation, after system reconfiguration, and after major maintenance.
§ 1065.310: torque	Upon initial installation and after major maintenance.
§ 1065.315: pressure, temperature, dew-point.	Upon initial installation and after major maintenance.
§ 1065.320: fuel flow	Upon initial installation and after major maintenance.
§ 1065.325: intake flow	Upon initial installation and after major maintenance.
§ 1065.330: exhaust flow	Upon initial installation and after major maintenance.
§ 1065.340: diluted exhaust flow (CVS)	Upon initial installation and after major maintenance.
§ 1065.341: CVS and batch sampler verification.	Upon initial installation, within 35 days before testing, and after major maintenance.
§ 1065.345: vacuum leak	Before each laboratory test according to subpart F of this part and before each field test according to subpart J of this part.