

§ 265.281

period the owner or operator of a land treatment unit must:

- (1) Continue soil-core monitoring by collecting and analyzing samples in a manner and frequency specified in the post-closure plan;
- (2) Restrict access to the unit as appropriate for its post-closure use;
- (3) Assure that growth of food chain crops complies with § 265.276; and
- (4) Control wind dispersal of hazardous waste.

[45 FR 33232, May 19, 1980, as amended at 47 FR 32368, July 26, 1982; 71 FR 16911, Apr. 4, 2006; 71 FR 40275, July 14, 2006]

§ 265.281 Special requirements for ignitable or reactive waste.

The owner or operator must not apply ignitable or reactive waste to the treatment zone unless the waste and treatment zone meet all applicable requirements of 40 CFR part 268, and:

(a) The waste is immediately incorporated into the soil so that:

(1) The resulting waste, mixture, or dissolution of material no longer meets the definition of ignitable or reactive waste under § 261.21 or § 261.23 of this chapter; and

(2) Section 264.17(b) is complied with; or

(b) The waste is managed in such a way that it is protected from any material or conditions which may cause it to ignite or react.

[47 FR 32368, July 26, 1982, as amended at 55 FR 22686, June 1, 1990; 71 FR 40275, July 14, 2006]

§ 265.282 Special requirements for incompatible wastes.

Incompatible wastes, or incompatible wastes and materials (see appendix V for examples), must not be placed in the same land treatment area, unless § 265.17(b) is complied with.

Subpart N—Landfills

§ 265.300 Applicability.

The regulations in this subpart apply to owners and operators of facilities that dispose of hazardous waste in landfills, except as § 265.1 provides otherwise. A waste pile used as a disposal facility is a landfill and is governed by this subpart.

§ 265.301 Design and operating requirements.

(a) The owner or operator of each new landfill unit, each lateral expansion of a landfill unit, and each replacement of an existing landfill unit must install two or more liners and a leachate collection and removal system above and between such liners, and operate the leachate collection and removal system, in accordance with § 264.301(c), unless exempted under § 264.301(d), (e), or (f) of this chapter.

(b) The owner or operator of each unit referred to in paragraph (a) of this section must notify the Regional Administrator at least sixty days prior to receiving waste. The owner or operator of each facility submitting notice must file a part B application within six months of the receipt of such notice.

(c) The owner or operator of any replacement landfill unit is exempt from paragraph (a) of this section if:

(1) The existing unit was constructed in compliance with the design standards of section 3004(o)(1)(A)(i) and (o)(5) of the Resource Conservation and Recovery Act; and

(2) There is no reason to believe that the liner is not functioning as designed.

(d) The double liner requirement set forth in paragraph (a) of this section may be waived by the Regional Administrator for any monofill, if:

(1) The monofill contains only hazardous wastes from foundry furnace emission controls or metal casting molding sand, and such wastes do not contain constituents which would render the wastes hazardous for reasons other than the Toxicity Characteristic in § 261.24 of this chapter, with EPA Hazardous Waste Numbers D004 through D017; and

(2)(i)(A) The monofill has at least one liner for which there is no evidence that such liner is leaking;

(B) The monofill is located more than one-quarter mile from an “underground source of drinking water” (as that term is defined in 40 CFR 270.2); and

(C) The monofill is in compliance with generally applicable ground-water monitoring requirements for facilities with permits under RCRA section 3005(c); or

Environmental Protection Agency

§ 265.302

(ii) The owner or operator demonstrates that the monofill is located, designed and operated so as to assure that there will be no migration of any hazardous constituent into ground water or surface water at any future time.

(e) In the case of any unit in which the liner and leachate collection system has been installed pursuant to the requirements of paragraph (a) of this section and in good faith compliance with paragraph (a) of this section and with guidance documents governing liners and leachate collection systems under paragraph (a) of this section, no liner or leachate collection system which is different from that which was so installed pursuant to paragraph (a) of this section will be required for such unit by the Regional Administrator when issuing the first permit to such facility, except that the Regional Administrator will not be precluded from requiring installation of a new liner when the Regional Administrator has reason to believe that any liner installed pursuant to the requirements of paragraph (a) of this section is leaking.

(f) The owner or operator must design, construct, operate, and maintain a run-on control system capable of preventing flow onto the active portion of the landfill during peak discharge from at least a 25-year storm.

(g) The owner or operator must design, construct, operate and maintain a run-off management system to collect and control at least the water volume resulting from a 24-hour, 25-year storm.

(h) Collection and holding facilities (e.g., tanks or basins) associated with run-on and run-off control systems must be emptied or otherwise managed expeditiously after storms to maintain design capacity of the system.

(i) The owner or operator of a landfill containing hazardous waste which is subject to dispersal by wind must cover or otherwise manage the landfill so that wind dispersal of the hazardous waste is controlled.

[*Comment:* As required by § 265.13, the waste analysis plan must include analyses needed to comply with §§ 265.312, 265.313, and 265.314. As required by § 265.73, the owner or operator

must place the results of these analyses in the operating record of the facility.]

[45 FR 33232, May 19, 1980, as amended at 47 FR 32368, July 26, 1982; 50 FR 18374, Apr. 30, 1985. Redesignated from § 265.302 at 57 FR 3494, Jan. 29, 1992; 50 FR 28750, July 15, 1985, as amended at 57 FR 3494, Jan. 29, 1992; 57 FR 30658, July 10, 1992; 71 FR 16911, Apr. 4, 2006; 71 FR 40275, July 14, 2006]

§ 265.302 Action leakage rate.

(a) The owner or operator of landfill units subject to § 265.301(a) must submit a proposed action leakage rate to the Regional Administrator when submitting the notice required under § 265.301(b). Within 60 days of receipt of the notification, the Regional Administrator will: Establish an action leakage rate, either as proposed by the owner or operator or modified using the criteria in this section; or extend the review period for up to 30 days. If no action is taken by the Regional Administrator before the original 60 or extended 90 day review periods, the action leakage rate will be approved as proposed by the owner or operator.

(b) The Regional Administrator shall approve an action leakage rate for landfill units subject to § 265.301(a). The action leakage rate is the maximum design flow rate that the leak detection system (LDS) can remove without the fluid head on the bottom liner exceeding 1 foot. The action leakage rate must include an adequate safety margin to allow for uncertainties in the design (e.g., slope, hydraulic conductivity, thickness of drainage material), construction, operation, and location of the LDS, waste and leachate characteristics, likelihood and amounts of other sources of liquids in the LDS, and proposed response actions (e.g., the action leakage rate must consider decreases in the flow capacity of the system over time resulting from siltation and clogging, rib layover and creep of synthetic components of the system, overburden pressures, etc.).

(c) To determine if the action leakage rate has been exceeded, the owner or operator must convert the weekly or monthly flow rate from the monitoring data obtained under § 265.304 to an average daily flow rate (gallons per acre per day) for each sump. Unless the Regional Administrator approves a different calculation, the average daily