ultimately must comply with the requirements of §§ 265.431 through 265.437. These sections are reserved at this time. The Agency will propose regulations that would establish those requirements.]

[45 FR 33232, May 19, 1980, as amended at 48 FR 30115, June 30, 1983]

Subparts S–V [Reserved]

Subpart W—Drip Pads

SOURCE: 55 FR 50486, Dec. 6, 1990, unless otherwise noted.

§ 265.440 Applicability.

(a) The requirements of this subpart apply to owners and operators of facilities that use new or existing drip pads to convey treated wood drippage, precipitation, and/or surface water run-off to an associated collection system. Existing drip pads are those constructed before December 6, 1990 and those for which the owner or operator has a design and has entered into binding financial or other agreements for construction prior to December 6, 1990. All other drip pads are new drip pads. The requirement at § 265.443(b)(3) to install a leak collection system applies only to those drip pads that are constructed after December 24, 1992 except for those constructed after December 24, 1992 for which the owner or operator has a design and has entered into binding financial or other agreements for construction prior to December 24, 1992.

(b) The owner or operator of any drip pad that is inside or under a structure that provides protection from precipitation so that neither run-off nor run-on is generated is not subject to regulation under § 265.443(e) or § 265.443(f), as appropriate.

(c) The requirements of this subpart are not applicable to the management of infrequent and incidental drippage in storage yards provided that:

(1) The owner or operator maintains and complies with a written contingency plan that describes how the owner or operator will respond immediately to the discharge of such infrequent and incidental drippage. At a minimum, the contingency plan must describe how the facility will do the following:

(i) Clean up the drippage;

(ii) Document the cleanup of the drippage;

(iii) Retain documents regarding cleanup for three years; and

(iv) Manage the contaminated media in a manner consistent with Federal regulations.

[55 FR 50486, Dec. 6, 1990, as amended by 56 FR 30198, July 1, 1991; 57 FR 61503, Dec. 24, 1992]

§ 265.441 Assessment of existing drip pad integrity.

(a) For each existing drip pad as defined in § 265.440, the owner or operator must evaluate the drip pad and determine that it meets all of the requirements of this subpart, except the requirements for liners and leak detection systems of § 265.443(b). No later than the effective date of this rule, the owner or operator must obtain and keep on file at the facility a written assessment of the drip pad, reviewed and certified by a qualified Professional Engineer that attests to the results of the evaluation. The assessment must be reviewed, updated, and re-certified annually until all upgrades, repairs, or modifications necessary to achieve compliance with all the standards of § 265.443 are complete. The evaluation must document the extent to which the drip pad meets each of the design and operating standards of § 265.443, except the standards for liners and leak detection systems, specified in § 265.443(b).

(b) The owner or operator must develop a written plan for upgrading, repairing, and modifying the drip pad to meet the requirements of § 265.443(b), and submit the plan to the Regional Administrator no later than 2 years before the date that all repairs, upgrades, and modifications are complete. This written plan must describe all changes to be made to the drip pad in sufficient detail to document compliance with all the requirements of § 265.443. The plan must be reviewed and certified by a qualified Professional Engineer.

(c) Upon completion of all repairs and modifications, the owner or operator must submit to the Regional Administrator or State Director, the as-built drawings for the drip pad together with a certification by a qualified Professional Engineer attesting

that the drip pad conforms to the drawings.

(d) If the drip pad is found to be leaking or unfit for use, the owner or operator must comply with the provisions of §265.443(m) of this subpart or close the drip pad in accordance with §265.445 of this subpart.

[55 FR 50486, Dec. 6, 1990, as amended at 57 FR 61504, Dec. 24, 1992; 71 FR 16912, Apr. 4, 2006; 71 FR 40276, July 14, 2006]

§ 265.442 Design and installation of new drip pads.

Owners and operators of new drip pads must ensure that the pads are designed, installed, and operated in accordance with one of the following:

(a) All of the applicable requirements of §§265.443 (except §265.443(a)(4)), 265.444 and 265.445 of this subpart, or

(b) All of the applicable requirements of §§265.443 (except §265.443(b)), 265.444 and 265.445 of this subpart.

[57 FR 61504, Dec. 24, 1992]

§ 265.443 Design and operating requirements.

(a) Drip pads must:

(1) Be constructed of non-earthen materials, excluding wood and non-structurally supported asphalt;

(2) Be sloped to free-drain treated wood drippage, rain and other waters, or solutions of drippage and water or other wastes to the associated collection system;

(3) Have a curb or berm around the perimeter;

(4)(i) Have a hydraulic conductivity of less than or equal to 1×10^{-7} centimeters per second, e.g., existing concrete drip pads must be sealed, coated, or covered with a surface material with a hydraulic conductivity of less than or equal to 1×10^{-7} centimeters per second such that the entire surface where drippage occurs or may run across is capable of containing such drippage and mixtures of drippage and precipitation, materials, or other wastes while being routed to an associated collection system. This surface material must be maintained free of cracks and gaps that could adversely affect its hydraulic conductivity, and the material must be chemically compatible with the preservatives that contact the drip pad. The requirements of this provision apply only to existing drip pads and those drip pads for which the owner or operator elects to comply with §265.442(b) instead of §265.442(a).

(ii) The owner or operator must obtain and keep on file at the facility a written assessment of the drip pad, reviewed and certified by a qualified Professional Engineer that attests to the results of the evaluation. The assessment must be reviewed, updated and recertified annually. The evaluation must document the extent to which the drip pad meets the design and operating standards of this section, except for paragraph (b) of this section.

(5) Be of sufficient structural strength and thickness to prevent failure due to physical contact, climatic conditions, the stress of installation, and the stress of daily operations, e.g., variable and moving loads such as vehicle traffic, movement of wood, etc.

NOTE: EPA will generally consider applicable standards established by professional organizations generally recognized by industry such as the American Concrete Institute (ACI) and the American Society of Testing Materials (ASTM) in judging the structural integrity requirement of this paragraph.

(b) If an owner/operator elects to comply with §265.442(a) instead of §265.442(b), the drip pad must have:

(1) A synthetic liner installed below the drip pad that is designed, constructed, and installed to prevent leakage from the drip pad into the adjacent subsurface soil or groundwater or surface water at any time during the active life (including the closure period) of the drip pad. The liner must be constructed of materials that will prevent waste from being absorbed into the liner and prevent releases into the adjacent subsurface soil or ground water or surface water during the active life of the facility. The liner must be:

(i) Constructed of materials that have appropriate chemical properties and sufficient strength and thickness to prevent failure due to pressure gradients (including static head and external hydrogeologic forces), physical contact with the waste or drip pad leakage to which they are exposed, climatic conditions, the stress of installation, and the stress of daily operation (including stresses from vehicular traffic on the drip pad);