

**§ 63.7810**

**40 CFR Ch. I (7-1-06 Edition)**

alarm is triggered, you must initiate corrective action to determine the cause of the alarm within 1 hour of the alarm, initiate corrective action to correct the cause of the problem within 24 hours of the alarm, and complete the corrective action as soon as practicable. Corrective actions may include, but are not limited to:

- (i) Inspecting the baghouse for air leaks, torn or broken bags or filter media, or any other condition that may cause an increase in emissions.
- (ii) Sealing off defective bags or filter media.
- (iii) Replacing defective bags or filter media or otherwise repairing the control device.
- (iv) Sealing off a defective baghouse compartment.
- (v) Cleaning the bag leak detection system probe, or otherwise repair the bag leak detection system.
- (vi) Shutting down the process producing the particulate emissions; and
- (5) Procedures for determining and recording the daily sinter plant production rate in tons per hour.

GENERAL COMPLIANCE REQUIREMENTS

**§ 63.7810 What are my general requirements for complying with this subpart?**

- (a) You must be in compliance with the emission limitations and operation and maintenance requirements in this subpart at all times, except during periods of startup, shutdown, and malfunction as defined in § 63.2.
- (b) During the period between the compliance date specified for your affected source in § 63.7783 and the date upon which continuous monitoring systems have been installed and certified and any applicable operating limits have been set, you must maintain a log detailing the operation and maintenance of the process and emissions control equipment.
- (c) You must develop a written startup, shutdown, and malfunction plan according to the provisions in § 63.6(e)(3).

[68 FR 27663, May 20, 2003, as amended at 71 FR 20468, Apr. 20, 2006]

INITIAL COMPLIANCE REQUIREMENTS

**§ 63.7820 By what date must I conduct performance tests or other initial compliance demonstrations?**

- (a) You must conduct a performance test to demonstrate initial compliance with each emission and opacity limit in Table 1 to this subpart that applies to you. You must also conduct a performance test to demonstrate initial compliance with the 30-day rolling average operating limit for the oil content of the sinter plant feedstock in § 63.7790(d)(1) or alternative limit for volatile organic compound emissions from the sinter plant windbox exhaust stream in § 63.7790(d)(2). You must conduct the performance tests within 180 calendar days after the compliance date that is specified in § 63.7783 for your affected source and report the results in your notification of compliance status.
- (b) For each operation and maintenance requirement that applies to you where initial compliance is not demonstrated using a performance test or opacity observation, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified for your affected source in § 63.7783.
- (c) If you commenced construction or reconstruction between July 13, 2001 and May 20, 2003, you must demonstrate initial compliance with either the proposed emission limit or the promulgated emission limit no later than November 17, 2003 or no later than 180 days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).
- (d) If you commenced construction or reconstruction between July 13, 2001 and May 20, 2003, and you chose to comply with the proposed emission limit when demonstrating initial compliance, you must conduct a second performance test to demonstrate compliance with the promulgated emission limit by November 17, 2006, or no later than 180 days after startup of the source, whichever is later, according to § 63.7(a)(2)(ix).