Following the date on which the initial performance test is completed, the facility shall operate with a block average L/V ratio, as determined in § 63.564(i)(2), no more than 20 percent below the baseline L/V ratio.

(9) *Alternative control devices.* For sources complying with § 63.562(b)(2), (3), and (4), (c)(3) and (4), and (d)(2) with the use of a control technology other than the devices discussed in paragraphs (b)(4) through (8) of this section, the owner or operator of an affected source shall provide to the Administrator information describing the design and operation of the air pollution control system, including recommendations for the operating parameter(s) to be monitored to indicate proper operation and maintenance of the air pollution control system. Based on this information, the Administrator shall determine the operating parameter(s) to be established during the performance test. During the initial performance test required in paragraph (b)(1) of this section, the owner or operator shall determine the efficiency of the air pollution control system using the test methods in § 63.565(d). The device shall achieve at least the percent destruction efficiency or recovery efficiency required under § 63.562(b)(2), (3), and (4), (c)(3) and (4), and (d)(2). The owner or operator shall establish the operating parameter(s) approved by the Administrator. Following the date on which the initial performance test is complete, the facility shall operate either above or below a maximum or minimum operating parameter, as appropriate.

(10) *Emission estimation.* The owner or operator of a source subject to § 63.562(b)(2), (3), and (4) shall use the emission estimation procedures in § 63.565(l) to calculate HAP emissions.

(c) *Leak detection and repair for vapor collection systems and control devices.* The following procedures are required for all sources subject to § 63.562(b), (c), or (d).

(1) *Annual leak detection and repair for vapor collection systems and control devices.* The owner or operator of an affected source shall inspect and monitor all ductwork and piping and connections to vapor collection systems and control devices once each calendar year using Method 21.

(2) *Ongoing leak detection and repair for vapor collection systems and control devices.* If evidence of a potential leak is found by visual, audible, olfactory, or any other detection method, all ductwork and piping and connections to vapor collection systems and control devices shall be inspected to the extent necessary to positively identify the potential leak and any potential leaks shall be monitored within 5 days by Method 21. Each detection of a leak shall be recorded, and the leak shall be tagged until repaired.

(3) When a leak is detected, a first effort to repair the vapor collection system and control device shall be made within 15 days or prior to the next marine tank vessel loading operation, whichever is later.

§ 63.564 Monitoring requirements.

(a)(1) The owner or operator of an affected source shall comply with the monitoring requirements in § 63.8 of subpart A of this part in accordance with the provisions for applicability of subpart A to this subpart in Table 1 of § 63.560 and the monitoring requirements in this section.

(2) Each owner or operator of an affected source shall monitor the parameters specified in this section. All monitoring equipment shall be installed such that representative measurements of emissions or process parameters from the source are obtained. For monitoring equipment purchased from a vendor, verification of the operational status of the monitoring equipment shall include completion of the manufacturer's written specifications or recommendations for installation, operation, and calibration of the system.

(3) Except for system breakdowns, out-of-control periods, repairs, maintenance periods, calibration checks, and zero (low-level) and high-level calibration drift adjustments, all continuous parametric monitoring systems (CPMS) and CEMS shall be in continuous operation while marine tank vessel loading operations are occuring and shall meet minimum frequency of operation requirements. Sources monitoring by use of CEMS and CPMS shall complete a minimum of one cycle of

operation (sampling, analyzing, and/or data recording) for each successive 15-minute period.

(4) The owner or operator of a CMS installed in accordance with these emissions standards shall comply with the performance specifications either in performance specification (PS) 8 in 40 CFR part 60, appendix B for CEMS or in § 63.7(c)(6) of subpart A of this part for CPMS.

(5) A CEMS is out of control when the measured values (i.e., daily calibrations, multipoint calibrations, and performance audits) exceed the limits specified in either PS 8 or in § 63.8(c)(7) of subpart A of this part. The owner or operator of a CEMS that is out of control shall submit all information concerning out of control periods, including start and end dates and hours and descriptions of corrective actions taken, in the excess emissions and continuous monitoring system performance report required in § 63.567(e).

(b) *Vapor collection system of terminal.* Owners or operators of a source complying with § 63.563(a)(1) that uses a vapor collection system that contains valves that could divert a vent stream from a control device used to comply with the provisions of this subpart shall comply with paragraph (b)(1), (2), or (3) of this section.

(1) Measure and record the vent stream flowrate of each by-pass line once every 15 minutes. The owner or operator shall install, calibrate, maintain, and operate a flow indicator and data recorder. The flow indicator shall be installed immediately downstream of any valve (i.e., entrance to by-pass line) that could divert the vent stream from the control device to the atmosphere.

(2) Measure the vent stream flowrate of each by-pass line once every 15 minutes. The owner or operator shall install, calibrate, maintain, and operate a flow indicator with either an audio or visual alarm. The flow indicator and alarm shall be installed immediately downstream of any valve (i.e., entrance to by-pass line) that could divert the vent stream from the control device to the atmosphere. The alarm shall be checked every 6 months to demonstrate that it is functioning properly.

(3) Visually inspect the seal or closure mechanism once during each marine tank vessel loading operation and at least once every month to ensure that the valve is maintained in the closed position and that the vent stream is not diverted through the by-pass line; record all times when the car seals have been broken and the valve position has been changed. Each by-pass line valve shall be secured in the closed position with a car-seal or a lock-and-key type configuration.

(c) *Pressure/vacuum settings for the marine tank vessel's vapor collection equipment.* Owners or operators of a source complying with § 63.563(a)(3) shall measure continuously the operating pressure of the marine tank vessel during loading.

(d) *Loading at negative pressure.* Owners or operators of a source complying with § 63.563(a)(4)(iv) that load vessels at less than atmospheric pressure (i.e., negative gauge pressure) shall measure and record the loading pressure. The owner or operator shall install, calibrate, maintain, and operate a recording pressure measurement device (magnehelic gauge or equivalent device) and an audible and visible alarm system that is activated when the pressure vacuum specified in § 63.563(a)(4)(iv) is not attained. The owner or operator shall place the alarm system so that it can be seen and heard where cargo transfer is controlled. The owner or operator shall verify the accuracy of the pressure device once each calendar year with a reference pressure monitor (traceable to National Institute of Standards and Technology (NIST) standards or an independent pressure measurement device dedicated for this purpose).

(e) *Combustion device, except flare.* For sources complying with § 63.563(b)(4), use of a combustion device except a flare, the owner or operator shall comply with paragraph (e)(1), (2), or (3) of this section. Owners or operators complying with paragraphs (e)(2) or (3) shall also comply with paragraph (e)(4) of this section.

(1) *Outlet VOC concentration.* Monitor the VOC concentrations at the exhaust point of the combustion device and record the output from the system. For sources monitoring the outlet VOC

concentration established during the performance test, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each cycle (same time period or cycle as the performance test) and a 3-cycle block average concentration every third cycle. For sources monitoring the 1,000 ppmv VOC concentration for gasoline loading, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each hour and a 3-hour block average concentration every third hour. The owner or operator will install, calibrate, operate, and maintain a CEMS consistent with the requirements of PS 8 to measure the VOC concentration. The daily calibration requirements are required only on days when marine tank vessel loading operations occur.

(2) *Operating temperature determined during performance testing.* If the baseline temperature was established during the performance test, the data acquisition system shall record the temperature every 15 minutes and shall compute and record an average temperature each cycle (same time period or cycle of the performance test) and a 3-cycle block average every third cycle.

(3) *Manufacturer's recommended operating temperature.* If the baseline temperature is based on the manufacturer recommended operating temperature, the data acquisition system shall record the temperature every 15 minutes and shall compute and record an average temperature each hour and a 3-hour block average every third hour.

(4) *Temperature monitor.* The owner or operator shall install, calibrate, operate, and maintain a temperature monitor accurate to within ±5.6 °C (±10 °F) or within 1 percent of the baseline temperature, whichever is less stringent, to measure the temperature. The monitor shall be installed at the exhaust point of the combustion device but not within the combustion zone. The owner or operator shall verify the accuracy of the temperature monitor once each calendar year with a reference temperature monitor (traceable to National Institute of Standards and Technology (NIST) standards or an independent temperature measurement device dedicated for this purpose). During accuracy checking, the probe of the reference device shall be at the same location as that of the temperature monitor being tested.

(f) *Flare.* For sources complying with § 63.563(b)(5), use of a flare, the owner or operator shall monitor and record continuously the presence of the flare pilot flame. The owner or operator shall install, calibrate, maintain, and operate a heat sensing device (an ultraviolet beam sensor or thermocouple) at the pilot light to indicate the presence of a flame during the entire loading cycle.

(g) *Carbon adsorber.* For sources complying with § 63.563(b)(6), use of a carbon adsorber, the owner or operator shall comply with paragraph (g)(1), (2), or (3) of this section.

(1) *Outlet VOC concentration.* Monitor the VOC concentrations at the exhaust point of each carbon adsorber unit and record the output from the system. For sources monitoring the outlet VOC concentration established during the performance test, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each cycle (same time period or cycle as the performance test) and a 3-cycle block average concentration every third cycle. For sources monitoring the 1,000 ppmv VOC concentration for gasoline loading, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each hour and a 3-hour block average concentration every third hour. The owner or operator will install, calibrate, operate, and maintain a CEMS consistent with the requirements of PS 8 to measure the VOC concentration. The daily calibration requirements are required only on days when marine tank vessel loading operations occur.

(2) *Carbon adsorbers with vacuum regeneration.* Monitor and record the regeneration time for carbon bed regeneration and monitor and record continuously the vacuum pressure of the carbon bed regeneration cycle. The owner or operator will record the time when the carbon bed regeneration cycle begins and when the cycle ends for a single carbon bed and will calculate a

3-cycle block average every third cycle. The owner or operator shall install, calibrate, maintain, and operate a recording pressure measurement device (magnehelic gauge or equivalent device). A data acquisition system shall record and compute a 3-cycle (carbon bed regeneration cycle) block average vacuum pressure every third cycle. The owner or operator shall verify the accuracy of the pressure device once each calendar year with a reference pressure monitor (traceable to National Institute of Standards and Technology (NIST) standards or an independent pressure measurement device dedicated for this purpose). During accuracy checking, the probe of the reference device shall be at the same location as that of the pressure monitor being tested.

(3) *Carbon adsorbers with steam regeneration.* Monitor and record the total stream mass flow and monitor and record the carbon bed temperature after regeneration (but within 15 minutes of completion of the cooling cycle). The owner or operator will install, calibrate, maintain, and operate an integrating stream flow monitoring device that is accurate within ±10 percent and that is capable of recording the total stream mass flow for each regeneration cycle. The owner or operator will install, calibrate, maintain, and operate a temperature monitor accurate to within ±5.6 °C (10 °F) or within 1 percent of the baseline carbon bed temperature, whichever is less stringent, to measure the carbon bed temperature. The monitor shall be installed at the exhaust point of the carbon bed. The data acquisition system shall record the carbon bed temperature after each cooling cycle (measured within 15 minutes of completion of the cooling cycle). The owner or operator shall verify the accuracy of the temperature monitor once each calendar year with a reference temperature monitor (traceable to National Institute of Standards and Technology (NIST) standards or an independent temperature measurement device dedicated for this purpose). During accuracy checking, the probe of the reference device shall be at the same location as that of the temperature monitor being tested.

(h) *Condenser/refrigeration unit.* For sources complying with § 63.563(b)(7), use of a condenser/refrigeration unit, the owner or operator shall comply with either paragraph (h)(1) or (2) of this section.

(1) *Baseline temperature.* Monitor and record the temperature at the outlet of the unit. The owner or operator shall install, calibrate, operate, and maintain a temperature monitor accurate to within ±5.6 °C (±10 °F) or within 1 percent of the baseline temperature, whichever is less stringent, to measure the temperature. The monitor shall be installed at the exhaust point of the condenser/refrigeration unit. For sources monitoring the temperature established during the performance test, the data acquisition system shall record the temperature every 15 minutes and shall compute and record an average temperature each cycle (same time period or cycle of the performance test) and a 3-hour block average every third cycle. For sources monitoring the manufacturer recommended temperature, the data acquisition system shall record the temperature every 15 minutes and shall compute and record an average temperature each hour and a 3-hour block average every third hour. The owner or operator shall verify the accuracy of the temperature monitor once each calendar year with a reference temperature monitor (traceable to National Institute of Standards and Technology (NIST) standards or an independent temperature measurement device dedicated for this purpose). During accuracy checking, the probe of the reference device shall be at the same location as that of the temperature monitor being tested.

(2) *Outlet VOC concentration.* Monitor the VOC concentrations at the outlet of the unit and record the output from the system. For sources monitoring the outlet VOC concentration established during the performance test, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each cycle (same time period or cycle as the performance test) and a 3-cycle block average concentration every third cycle. For sources monitoring the 1,000 ppmv VOC concentration for gasoline loading, a data

acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each hour and a 3-hour block average concentration every third hour. The owner or operator will install, calibrate, operate, and maintain a VOC CEMS consistent with the requirements of PS 8 to measure the VOC concentration. The daily calibration requirements are required only on days when marine tank vessel loading operations occur.

(i) *Absorber*. For sources complying with § 63.563(b)(8), use of an absorber, the owner or operator shall comply with either paragraph (i)(1) or (2) of this section.

(1) *Outlet VOC concentration*. Monitor the VOC concentrations at the outlet of the absorber and record the output from the system. For sources monitoring the outlet VOC concentration established during the performance test, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each cycle (same time period or cycle as the performance test) and a 3-cycle block average concentration every third cycle. For sources monitoring the 1,000 ppmv VOC concentration for gasoline loading, a data acquisition system shall record a concentration every 15 minutes and shall compute and record an average concentration each hour and a 3-hour block average concentration every third hour. The owner or operator will install, calibrate, operate, and maintain a VOC CEMS consistent with the requirements of PS 8. The daily calibration requirements are required only on days when marine tank vessel loading operations occur.

(2) *L/V ratio*. Monitor and record the inlet liquid flowrate and the inlet gas flowrate to the absorber and record the calculated L/V ratio. The owner or operator shall install, calibrate, maintain, and operate liquid and gas flow indicators. For sources monitoring the L/V ratio established during the performance test, a data acquisition system shall record the flowrates and calculated ratio every 15 minutes and shall compute and record an average ratio each cycle (same time period or cycle as the performance test) and a 3-cycle block average ratio every third cycle. For sources monitoring the manufacturer recommended L/V ratio, a data acquisition system shall record the flowrates and calculated ratio every 15 minutes and shall compute and record an average ratio each hour and a 3-hour average ratio every third hour. The liquid and gas flow indicators shall be installed immediately upstream of the respective inlet lines to the absorber.

(j) *Alternate monitoring procedures*. Alternate procedures to those described in this section may be used upon application to, and approval by, the Administrator. The owner or operator shall comply with the procedures for use of an alternative monitoring method in § 63.8(f).

§ 63.565 Test methods and procedures.

(a) *Performance testing*. The owner or operator of an affected source in § 63.562 shall comply with the performance testing requirements in § 63.7 of subpart A of this part in accordance with the provisions for applicability of subpart A to this subpart in Table 1 of § 63.560 and the performance testing requirements in this section.

(b) *Pressure/vacuum settings of marine tank vessel's vapor collection equipment*. For the purpose of determining compliance with § 63.563(a)(3), the following procedures shall be used:

(1) Calibrate and install a pressure measurement device (liquid manometer, magnehelic gauge, or equivalent instrument) capable of measuring up to the maximum relief set pressure of the pressure-vacuum vents;

(2) Connect the pressure measurement device to a pressure tap in the terminal's vapor collection system, located as close as possible to the connection with the marine tank vessel; and

(3) During the performance test required in § 63.563(b)(1), record the pressure every 5 minutes while a marine tank vessel is being loaded and record the highest instantaneous pressure and vacuum that occurs during each loading cycle.

(c) *Vapor-tightness test procedures for the marine tank vessel*. When testing a vessel for vapor tightness to comply with the marine vessel vapor-tightness