

Environmental Protection Agency

§ 63.7734

TEA sampling run in intervals of no more than 15 minutes.

(2) Compute and record the average scrubbing liquid flow rate for each valid sampling run in which the applicable emissions limit is met.

(e) You may change the operating limits for a capture system, wet scrubber, acid wet scrubber, or combustion device if you meet the requirements in paragraphs (e)(1) through (3) of this section.

(1) Submit a written notification to the Administrator of your request to conduct a new performance test to revise the operating limit.

(2) Conduct a performance test to demonstrate compliance with the applicable emissions limitation in § 63.7690.

(3) Establish revised operating limits according to the applicable procedures in paragraphs (a) through (d) of this section.

(f) You may use a previous performance test (conducted since December 22, 2002) to establish an operating limit provided the test meets the requirements of this subpart.

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008]

§ 63.7734 How do I demonstrate initial compliance with the emissions limitations that apply to me?

(a) You have demonstrated initial compliance with the emissions limits in § 63.7690(a) by meeting the applicable conditions in paragraphs (a)(1) through (11) of this section. When alternative emissions limitations are provided for a given emissions source, you are not restricted in the selection of which applicable alternative emissions limitation is used to demonstrate compliance.

(1) For each electric arc metal melting furnace, electric induction metal melting furnace, or scrap preheater at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.005 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the perform-

ance test procedures in § 63.7732(c), did not exceed 0.0004 gr/dscf.

(2) For each cupola metal melting furnace at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.006 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0005 gr/dscf; or

(iii) The average PM mass emissions rate, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.10 pound of PM per ton (lb/ton) of metal charged; or

(iv) The average total metal HAP mass emissions rate, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.008 pound of total metal HAP per ton (lb/ton) of metal charged.

(3) For each cupola metal melting furnace or electric arc metal melting furnace at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.002 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0002 gr/dscf.

(4) For each electric induction metal melting furnace or scrap preheater at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(b), did not exceed 0.001 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.00008 gr/dscf.

(5) For each pouring station at an existing iron and steel foundry,

(i) The average PM concentration in the exhaust stream, measured according to the performance test procedures

§ 63.7734

40 CFR Ch. I (7-1-08 Edition)

in § 63.7732(b), did not exceed 0.010 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0008 gr/dscf.

(6) For each pouring area or pouring station at a new iron and steel foundry,

(i) The average PM concentration in the exhaust stream, measured according to the performance test procedures in § 63.7732(b), did not exceed 0.002 gr/dscf; or

(ii) The average total metal HAP concentration in the exhaust stream, determined according to the performance test procedures in § 63.7732(c), did not exceed 0.0002 gr/dscf.

(7) For each building or structure housing any iron and steel foundry emissions source at the iron and steel foundry, the opacity of fugitive emissions from foundry operations discharged to the atmosphere, determined according to the performance test procedures in § 63.7732(d), did not exceed 20 percent (6-minute average), except for one 6-minute average per hour that did not exceed 27 percent opacity.

(8) For each cupola metal melting furnace at a new or existing iron and steel foundry, the average VOHAP concentration, determined according to the performance test procedures in § 63.7732(e), did not exceed 20 ppmv corrected to 10 percent oxygen.

(9) For each scrap preheater at an existing iron and steel foundry that does not meet the work practice standards in § 63.7700(e)(1) or (2) and for each scrap preheater at a new iron and steel foundry that does not meet the work practice standard in § 63.7700(f), the average VOHAP concentration determined according to the performance test procedures in § 63.7732(e), did not exceed 20 ppmv.

(10) For one or more automated conveyor and pallet cooling lines that use a sand mold system or automated shakeout lines that use a sand mold system at a new foundry,

(i) You have reduced the data from the CEMS to 3-hour averages according to the performance test procedures in § 63.7732(f)(1) or (2); and

(ii) The 3-hour flow-weighted average VOHAP concentration, measured ac-

ording to the performance test procedures in § 63.7332(f)(1) or (2), did not exceed 20 ppmv.

(11) For each TEA cold box mold or core making line in a new or existing iron and steel foundry, the average TEA concentration, determined according to the performance test procedures in § 63.7732(g), did not exceed 1 ppmv or was reduced by 99 percent.

(b) You have demonstrated initial compliance with the operating limits in § 63.7690(b) if:

(1) For each capture system subject to the operating limit in § 63.7690(b)(1)(ii),

(i) You have established appropriate site-specific operating limits in your operation and maintenance plan according to the requirements in § 63.7710(b); and

(ii) You have a record of the operating parameter data measured during the performance test in accordance with § 63.7733(a); and

(2) For each wet scrubber subject to the operating limits in § 63.7690(b)(2) for pressure drop and scrubber water flow rate, you have established appropriate site-specific operating limits and have a record of the pressure drop and scrubber water flow rate measured during the performance test in accordance with § 63.7733(b).

(3) For each combustion device subject to the operating limit in § 63.7690(b)(3) for combustion zone temperature, you have a record of the combustion zone temperature measured during the performance test in accordance with § 63.7732(e)(4).

(4) For each combustion device subject to the operating limit in § 63.7690(b)(4) for combustion zone temperature, you have established appropriate site-specific operating limits and have a record of the combustion zone temperature measured during the performance test in accordance with § 63.7733(c).

(5) For each acid wet scrubber subject to the operating limits in § 63.7690(b)(5) for scrubbing liquid flow rate and scrubber blowdown pH,

(i) You have established appropriate site-specific operating limits for the scrubbing liquid flow rate and have a record of the scrubbing liquid flow rate

Environmental Protection Agency

§ 63.7736

measured during the performance test in accordance with § 63.7733(d); and

(ii) You have a record of the pH of the scrubbing liquid blowdown measured during the performance test in accordance with § 63.7732(g)(3).

[69 FR 21923, Apr. 22, 2004, as amended at 73 FR 7221, Feb. 7, 2008]

§ 63.7735 How do I demonstrate initial compliance with the work practice standards that apply to me?

(a) For each iron and steel foundry subject to the certification requirement in § 63.7700(b), you have demonstrated initial compliance if you have certified in your notification of compliance status that: "At all times, your foundry will purchase and use only metal ingots, pig iron, slitter, or other materials that do not include post-consumer automotive body scrap, post-consumer engine blocks, post-consumer oil filters, oily turnings, lead components, mercury switches, plastics, or free organic liquids."

(b) For each iron and steel foundry subject to the requirements in § 63.7700(c) for a scrap inspection and selection plan, you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have submitted a written plan to the Administrator for approval according to the requirements in § 63.7700(c); and

(2) You will operate at all times according to the plan requirements.

(c) For each furan warm box mold or core making line in a new or existing foundry subject to the work practice standard in § 63.7700(d), you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You will meet the no methanol requirement for the catalyst portion of each binder chemical formulation; and

(2) You have records documenting your certification of compliance, such as a material safety data sheet (provided that it contains appropriate information), a certified product data sheet, or a manufacturer's hazardous air pollutant data sheet, onsite and available for inspection.

(d) For each scrap preheater at an existing iron and steel foundry subject to

the work practice standard in § 63.7700(e)(1) or (2), you have demonstrated initial compliance if you have certified in your notification of compliance status that:

(1) You have installed a gas-fired preheater where the flame directly contacts the scrap charged, you will operate and maintain each gas-fired scrap preheater such that the flame directly contacts the scrap charged, and you have records documenting your certification of compliance that are onsite and available for inspection; or

(2) You will charge only material that is subject to and in compliance with the scrap certification requirements in § 63.7700(b) and you have records documenting your certification of compliance that are onsite and available for inspection.

(e) For each scrap preheater at a new iron and steel foundry subject to the work practice standard in § 63.7700(f), you have demonstrated initial compliance if you have certified in your notification of compliance status that you will charge only material that is subject to and in compliance with the scrap certification requirements in § 63.7700(b) and you have records documenting your certification of compliance that are onsite and available for inspection.

[69 FR 21923, Apr. 22, 2004, as amended at 70 FR 29404, May 20, 2005]

§ 63.7736 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?

(a) For each capture system subject to an operating limit in § 63.7690(b), you have demonstrated initial compliance if you have met the conditions in paragraphs (a)(1) and (2) of this section.

(1) You have certified in your notification of compliance status that:

(i) You have submitted the capture system operation and maintenance plan to the Administrator for approval according to the requirements of § 63.7710(b); and

(ii) You will inspect, operate, and maintain each capture system according to the procedures in the plan.

(2) You have certified in your performance test report that the system