

## Environmental Protection Agency

## § 63.8232

records for these procedures as specified in Table 9 to this subpart.

(A) Within 1 hour of the time the action level was exceeded, you must conduct each inspection specified in Table 2 to this subpart, with the exception of the cell room floor and the pillars and beam inspections. You must correct any problem identified during these inspections in accordance with the requirements in Table 2 and 3 to this subpart.

(B) If the Table 2 inspections and subsequent corrective actions do not reduce the mercury concentration below the action level, you must inspect all decomposers, hydrogen system piping up to the hydrogen header, and other potential locations of mercury vapor leaks using a technique specified in Table 6 to this subpart. If a mercury vapor leak is identified, you must take the appropriate action specified in Table 3 to this subpart.

### OPERATION AND MAINTENANCE REQUIREMENTS

#### § 63.8222 What are my operation and maintenance requirements?

As required by § 63.6(e)(1)(i), you must always operate and maintain your affected source(s), including air pollution control and monitoring equipment, in a manner consistent with safety and good air pollution control practices for minimizing emissions.

### GENERAL COMPLIANCE REQUIREMENTS

#### § 63.8226 What are my general requirements for complying with this subpart?

(a) You must be in compliance with the applicable emission limitations for by-product hydrogen streams, end box ventilation system vents, and mercury thermal recovery unit vents in § 63.8190 at all times, except during periods of startup, shutdown, and malfunction. You must be in compliance with the applicable work practice standards in § 63.8192 at all times, except during periods of startup, shutdown, and malfunction.

(b) You must develop a written startup, shutdown, and malfunction plan

(SSMP) according to the provisions in § 63.6(e)(3).

[68 FR 70928, Dec. 19, 2003, as amended at 71 FR 20469, Apr. 20, 2006]

### INITIAL COMPLIANCE REQUIREMENTS

#### § 63.8230 By what date must I conduct performance tests or other initial compliance demonstrations?

(a) You must conduct a performance test no later than the compliance date that is specified in § 63.8186 for your affected source to demonstrate initial compliance with the applicable emission limit in § 63.8190(a)(2) for by-product hydrogen streams and end box ventilation system vents and the applicable emission limit in § 63.8190(a)(3) for mercury thermal recovery unit vents.

(b) For the applicable work practice standards in § 63.8192, you must demonstrate initial compliance within 30 calendar days after the compliance date that is specified for your affected source in § 63.8186.

#### § 63.8232 What test methods and other procedures must I use to demonstrate initial compliance with the emission limits?

You must conduct a performance test for each by-product hydrogen stream, end box ventilation system vent, and mercury thermal recovery unit vent according to the requirements in § 63.7(e)(1) and the conditions detailed in paragraphs (a) through (d) of this section.

(a) You may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in § 63.7(e)(1).

(b) For each performance test, you must develop a site-specific test plan in accordance with § 63.7(c)(2).

(c) You must conduct at least three test runs to comprise a performance test, as specified in § 63.7(e)(3) and in either paragraph (c)(1) or (2) of this section.

(1) The sampling time and sampling volume for each run must be at least 2 hours and 1.70 dry standard cubic meters (dscm). Mercury results below the analytical laboratory's detection limit must be reported using the reported analytical detection limit to calculate the sample concentration value and, in