

(f) The shore terminal or the other tank vessel concerned has reported itself in readiness for transfer of cargo.

(g) All sea valves connected to the cargo piping system are closed.

(h) In loading Grades A, B, and C cargoes, that an inspection has been made to determine whether boiler fires can be maintained with reasonable safety.

(i) In loading Grades A, B, and C cargoes, that an inspection has been made to determine whether galley fires can be maintained with reasonable safety.

(j) In loading Grades A, B, or C cargoes, that an inspection has been made to determine whether smoking may be permitted with reasonable safety in areas other than the weather deck.

(k) On tankships the construction or conversion of which is started on or after July 1, 1951, which are to load or discharge Grade A cargo, all openings in the top of the tanks, except the branch vent lines and covers to ullage hole sounding pipes, are tightly closed. (See §§ 32.20–20 and 32.55–20 of this subchapter.)

(l) On tankships the construction or conversion of which is started on or after July 1, 1951, which are to load or discharge Grade A cargo, the method for determining the liquid level in the tank without opening ullage holes, cargo hatches or Butterworth plates is in proper order. (See § 32.20–20 of this subchapter.)

(m) When a transfer operation includes collection of cargo vapor from a vessel's cargo tanks through a vapor control system not located on the vessel:

(1) Each part of the vapor collection system is aligned to allow vapor to flow to a facility vapor control system, or if lightering, to the other vessel;

(2) Vapor collection hoses or arms are connected to the vessel vapor collection connection;

(3) The electrical insulation requirements of 33 CFR 154.810(g) or § 39.40–3(c) of this subchapter are provided between the vessel vapor connection and the facility or service vessel vapor connection;

(4) The maximum cargo transfer rate is determined in accordance with § 39.30–1(d) of this subchapter;

(5) The maximum and minimum operating pressures at the facility vapor

connection, or vessel vapor connection if lightering, are determined;

(6) The overfill control system on a tank barge, if fitted in accordance with § 39.20–9(b) of this subchapter, is connected to the facility, tested and operating properly;

(7) Each alarm required by §§ 39.20–7, 39.20–9 and 39.40–3(a) of this subchapter has been tested not more than 24 hours prior to the start of the transfer operation and is operating properly;

(8) Each vapor recovery hose has no unrepaired loose covers, kinks, bulges, soft spots, or any other defect which would permit the discharge of vapors through the hose material, and no gouges, cuts, or slashes that penetrate the first layer of hose reinforcement; and

(9) The oxygen content of the vessel's cargo tanks, if inerted, is at or below 8 percent by volume.

[CGFR 65–50, 30 FR 16704, Dec. 30, 1965, as amended by CGD 80–009, 48 FR 36459, Aug. 11, 1983; CGD 88–102, 55 FR 25446, June 21, 1990; CGD 79–116, 60 FR 17156, Apr. 4, 1995]

§ 35.35–25 Approval to start transfer of cargo—TB/ALL.

When the person in charge of the transfer of liquid cargo in bulk has ensured that the requirements of §§ 35.35–20 and 35.35–30 have been met, he or she may give approval to start the transfer.

[CGD 79–116, 60 FR 17156, Apr. 4, 1995]

§ 35.35–30 “Declaration of Inspection” for tank vessels—TB/ALL.

(a) After an inspection under § 35.35–20, but before a transfer of cargo, fuel oil, or bunkers may commence as described in this section and 33 CFR 156.120 and 156.150, the person in charge of the transfer shall prepare, in duplicate, a Declaration of Inspection. The original must be kept aboard the vessel, and the duplicate provided to the terminal supervisor or that person's representative. The supervisor or the representative may, upon demand, inspect the vessel to determine whether its condition is as stated on the Declaration of Inspection.

(b) The Declaration of Inspection may be in any form, but must contain at least: