(d) The design and construction of the cargo tanks shall be at least equivalent to the standards established by the American Bureau of Shipping or other recognized classification society. For special tanks, or designs not contemplated by standards of the classification society, a detailed analysis of the entire tank, or designated parts thereof, shall be made and submitted to the Commandant for approval.

(e) The cargo tank shall be designed for a head of cargo at least equal to the highest level the liquid cargo may attain plus the maximum venting pressure. In no case shall a head of cargo less than 4 feet above the cargo hatch or expansion trunk be used.

(f) The design shall investigate the thermal stresses induced in the cargo tank during loading. Where necessary, devices for spray loading or other methods of precooling or cooling during loading shall be included in the design.

(g) All weld intersections or crossings in joints of primary tank shells shall be radiographed for a distance of 10 thicknesses from the intersection. All other welding in the primary tank and in the secondary barrier shall be spot radiographed in accordance with the requirements of part 54 of subchapter F (Marine Engineering) of this chapter.

[CGFR 66–33, 31 FR 15269, Dec. 6, 1966, as amended by CGFR 68–82, 33 FR 18807, Dec. 18, 1968]

§ 38.05–5 Markings—TB/ALL.

(a)(1) Upon satisfactory completion of tests and inspection, pressure vessel and nonpressure vessel type cargo tanks, shall have markings as required by § 54.10–20 of subchapter F (Marine Engineering) of this chapter except that for nonpressure vessel type tanks, the Coast Guard number and pressure vessel class shall be omitted.

(2) Hydrostatic test for pressure vessel type tanks shall be that specified in § 38.25–1(b). In the case of nonpressure vessel type tanks, the hydrostatic test pressure shall mean the pressure specified in § 38.25–1(d), while the maximum allowable pressure shall mean the maximum venting pressure as used in § 38.05–4(e). Where it is not feasible to attach the nameplate to the tank, it shall be conspicuously displayed nearby.

(b) All tank inlet and outlet connections, except safety relief valves, liquid level gaging devices, and pressure gages, shall be labeled to designate whether they terminate in the vapor or liquid space. Labels of corrosion-resistant material may be attached to valves.

(c) All tank markings shall be permanently and legibly stamped in a readily visible position, and shall not be obscured by painting. If the tanks are lagged, the markings attached to the tank proper shall be duplicated on a corrosion-resistant plate secured to the outside jacket of the lagging.

[CGFR 66–33, 31 FR 15269, Dec. 6, 1966, as amended by CGFR 68–82, 33 FR 18807, Dec. 18, 1968]

§ 38.05–10 Installation of cargo tanks—general—TB/ALL.

(a)(1) Cargo tanks shall be supported on foundations of steel or other suitable material and securely anchored in place to prevent the tanks from shifting when subjected to external forces. Each tank shall be so supported as to prevent the concentration of excessive loads on the supporting portions of the shell or head as prescribed under § 38.05–2(d).

(2) Cargo tanks installed in barges shall comply with the requirements of § 32.63–25 of this subchapter.

(b) Foundations, and stays where required, shall be designed for support and constraint of the weight of the full tank, and the dynamic loads imposed thereon. Thermal movement shall also be considered.

(c) Foundations and stays which may be exposed to the cargo shall be suitable for the temperatures involved and be impervious to the cargo.

(d) The design of the foundations and stays shall consider the resonance of the cargo tank, or parts thereof, and the vibratory forces, found in the tank vessel. If necessary, effective damping arrangements shall be provided.

(e) Independent containment systems shall be so arranged as to provide a minimum clearance of not less than 24 inches from the vessel's side and not less than 15 inches from the vessel's bottom to provide access for inspection